


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

KINGMAN County, Sec. 20 Twp. 28S Rge. 8E (E) (W)

Location as "NE/CNW/SW" or footage from lines C NE SE
Lease Owner Mercury Drilling Company
Lease Name BARKER Well No. 1
Office Address 707 Enterprise Building, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 21, 19 64
Application for plugging filed July 21, 19 64
Application for plugging approved July 21, 19 64
Plugging commenced July 22, 19 64
Plugging completed July 22, 19 64
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Herman E. Justus, Nickerson, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4431 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Sand, Redbed & Shale</u>	<u>Surface Casing</u>	<u>-0-</u>	<u>223'</u>	<u>8-5/8"</u>	<u>223'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED HOLE: Filled hole with mud up to 225',
bridge, plug & 25 sx. cement.
Filled hole to 40', bridge, plug
& 10 sx. cement. Put 2 sx. in
rathole. Finished at 9 a.m., 7-22-64.

RECEIVED
STATE CORPORATION COMMISSION

JUL 28 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor SIERRA PETROLEUM CO., INC.
Address 1015 Wichita Plaza Bldg., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
S. P. Hall, Superintendent (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. P. Hall
S. P. Hall, Superintendent

Box 232, Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of July, 19 64

My commission expires 10-17-67

LeRoy Dick
Notary Public.

MERCURY DRILLING CO. - Operator

SINORA PETRO. CO., INC. - Contractor

BARKER #1
C NE SE
Sec. 20-28S-8E
Kingman County, Kansas

T. D.: 4431'

Commenced: 7-11-64
Completed: 7-21-64

Gas ing:

Cement:

8-5/8" Set at 223' K.B.

with 175 ex. HA-5

FORMATION

DEPTH

Sand & Redbed	100
Redbed & Shale	690
Shells & Shale	1490
Shale & Lime Streaks	1554
Shale & Lime	3305
Sand & Lime	3430
Lime	4050
Chert & Lime	4124
Lime	4180
Lime & Shale	4394
Lime	4431

RECEIVED
STATE CORPORATION COMMISSION

JUL 28 1964

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) SS:
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

S. P. Hall
Superintendent

Subscribed and sworn to before me this 27th day of July, 1964.

Lesley Dietz
Notary Public

My commission expires: 10-17-67.