


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-051-30004-1000
WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Ellis County. Sec. 1 Twp. 13 Rge. 18 (X) (W)
Location as "NE/CNWSW" or footage from lines NE SW SE
Lease Owner Leo J. Dreiling Oil Company
Lease Name Ubert "B" Well No. _____
Office Address Victoria, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed 1- 21- 65 19_____
Application for plugging filed 1- 21- 65 19_____
Application for plugging approved 1- 21- 65 19_____
Plugging commenced 1- 21- 65 19_____
Plugging completed 1- 21- 65 19_____
Reason for abandonment of well or producing formation -0-

If a producing well is abandoned, date of last production -0- 19_____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Truan Russell, Kansas
Producing formation -0- Depth to top 0 Bottom 0 Total Depth of Well 3613' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SURFACE PIPE				8-5/8"	130'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with rotary mud to a depth of 420' where 1st plug was set using 20 sacks cement. Filling hole with rotary mud to a depth of 120' where 2nd plug was set using 20 sacks cement. Rotary mud was used to fill hole to a depth of 40' where 3rd plug was set using 10 sax cement and filling hole to surface.

RECEIVED
STATE CORPORATION COMMISSION
FEB 1 1965
02-01-65
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor L. J. Dreiling & Sons, Inc.
Address Victoria, Kansas

STATE OF Kansas, COUNTY OF Ellis, ss.
I, Leo F. Dreiling, a partner (Signature) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling Victoria, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28 day of January, 19 65

My commission expires October 26, 1968 Elmer W. Kelly Notary Public.

R

L. J. DREILING and SONS, Inc.
VICTORIA, KANSAS

WELL LOG

Company Leo J. Dreiling Oil Co. Victoria, Kansas	Sec. 1	Twp. 13	Rng. 18
Farm Ubert B No. # 3	Location NE / SW / SE		
Total Depth 3613'	County Ellis		
Comm. 1 - 15 - 65	Comp. 1 - 21 - 65	Elevation: 2050'	D. F.
Contractor L. J. Dreiling & Sons, Inc. Victoria, Kansas		2053'	G. R.
Casing Record	Cement Record	Production:	
130' 8-5/8"	80 sax	D & A	

Figures Indicate Bottom of Formations

0'	40'	Surface Soil & Gravel
40'	130'	Shale
130'	200'	Shale
200'	562'	Shale
562'	677'	Sand
677'	944'	Shale & Sand
944'	1282'	Shale
1282'	1290'	Shale & Redbed
1290'	1325'	Anhy.
1325'	1948'	Shale & Shells
1948'	2015'	Shale & Lime
2015'	2164'	Lime & Shale
2164'	2339'	Lime & Shale
2339'	2550'	Shale & Lime
2550'	2753'	Shale & Lime
2753'	2870'	Lime & Shale
2870'	3065'	Lime & Shale
3065'	3148'	Lime & Shale
3148'	3243'	Lime & Shale
3243'	3332'	Lime
3332'	3380'	Lime
3380'	3460'	Lime
3460'	3472'	Lime
3472'	3505'	Lime
3505'	3554'	Lime
3554'	3613'	Lime & Shale
3613'	T.D.	

RECORDED
 FEB 11 1965
 STATE OF KANSAS
 DEPARTMENT OF REVENUE

STATE OF KANSAS)
) ss
 County Of ELLIS)

L, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Ubert B # 3.


 LEO F. DREILING

Subscribed and sworn to before me this 20th Day of January, 1965.


 NOTARY PUBLIC

My Commission Expires: October 26, 1968