


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
860 Bitting Building  
Wichita, Kansas

15051-19131-00-00  
**WELL PLUGGING RECORD**

NORTH



Locate well correctly on above  
Section Plat

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW SE  
Lease Owner The Vickers Petroleum Co., Inc.  
Lease Name Ubert Well No. 1  
Office Address 201 W-K-H Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed April 26 19 38  
Application for plugging filed July 13 19 50  
Application for plugging approved July 13 19 50  
Plugging commenced July 14 19 50  
Plugging completed July 15 19 50  
Reason for abandonment of well or producing formation Depleted  
If a producing well is abandoned, date of last production May 14 19 50  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Elson Petty, Hays, Kansas  
Producing formation Arbuckle Depth to top 3577 Bottom 3610 Total Depth of Well 3610 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				12 $\frac{1}{2}$ "	96'	None
				5 $\frac{1}{2}$ "	3578'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Dump 6sx cement on bottom @ 3610', Filled to 3570', Filled w/mud to 200',  
Set plug. Dumped 12 sx cement. Filled w/mud to 30', Capped w/5 sx cement.

**RECEIVED**

Conservation Div.

JUL 19 1950

(If additional description is necessary, use BACK of this sheet.)

STATE CORPORATION COMMISSION

Correspondence regarding this well should be addressed to The Vickers Petroleum Co., Inc.  
Address 201 W-K-H Building, Wichita, Kansas KANSAS

STATE OF Kansas, COUNTY OF Sedgwick, ss.

John M. Little (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

John M. Little  
201 W-K-H Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of July, 19 50

My commission expires August 13, 1953

Alex Denton  
Notary Public.

**PLUGGING**  
FILE SEC L T 13 R 18w  
BOOK PAGE 17 LINE 1

THE VICKERS PETROLEUM CO., INC.

Ubert Well #1  
 SW SW SE Sec. 1-13S-18W  
 Ellis County, Kansas

Casing Record:  
 12½" @ 96' w/75 sx  
 5½" @ 3578 w/80 sx

Commenced: March 29, 1938  
 Completed: April 26, 1938

Elevation 2059  
 Potential: 1201 BOPD no water

LOG

Shale & Shells	0-430
Pyrite	430-435
Shale & Shells	435-745
Sand	745-960
Shale & Red Bed	960-1055
Shale & Shells	1055-1210
Lime & Red Bed	1210-1285
Anhydrite	1285-1295
Lime Hard	1295-1346
Lime Broken	1346-1375
Red Bed	1375-1465
Red Bed & Lime Shells	1465-1595
Shale & Shells	1595-1615
Red Shells	1615-1675
Salt	1675-1737
Shale & Shells	1737-1900
Lime & Shale	1900-2015
Shale & Lime	2015-2075
Lime & Red Shale	2075-2150
Lime & Shale	2150-2170
Lime	2170-2210
Lime & Shale	2210-2255
Shale & Shells	2255-2320
Lime	2320-2344
Lime Hard	2344-2388
Lime Broken	2388-2410
Lime & Shale	2410-2455
Shale & Lime	2455-2520
Lime	2520-2567
Lime & Shale	2567-2580
Lime	2580-2630
Lime & Shale	2630-2650
Lime	2650-2670
Lime & Shale	2670-2810
Shale & Shells	2810-2923
Shale & Lime	2923-2986
Lime & Shale	2986-3046
Lime	3046-3051
Lime Hard	3051-3058
Lime & Shale	3058-3105
Lime	3105-3189
Lime & Shale	3189-3222
Lime	3222-3278
Shale & Lime	3278-3310
Shale & Shells	3310-3323
Red Rock	3323-3332
Shale & Red Rock	3332-3334
Lime K.C.	3334-3470
Lime & Shale	3470-3565
Shale & Lime	3565-3573
Lime	3573-3580 RTD
Cable Tools:	
Lime	3588-3592
Green Shale	3592-3593
Lime	3593-3610 TD

Acidized through tubing w/5000 gal.

I hereby certify that this log is true and correct to the best of my knowledge and belief.

THE VICKERS PETROLEUM CO., INC.

By *John M. Ritter*

Sworn and subscribed to before me  
 this 17 day of July 1950

*Alex. Padenton*  
 Notary Public

**PLUGGING**  
 FILE SEC 1 T 13 R 80  
 BOOK PAGE 17 LINE 1

My commission expires Aug. 13, 1953.