

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15057-02820-00-00

API NUMBER N/A

LEASE NAME Crissman "A"

WELL NUMBER #3

990 Ft. from ^N Section Line

330 Ft. from ^W Section Line

SEC. 1 TWP. 13S RGE. 18 (X) or (W)

COUNTY Ellis

Date Well Completed 11/52

Plugging Commenced 5/10/99

Plugging Completed 5/10/99

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR H&B Petroleum Corporation

ADDRESS P.O. Box 536, Clearwater, Kansas 67026

PHONE (316)584-6463 OPERATORS LICENSE NO. 32158

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5/10/99 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? Unk. If not, is well log attached? Yes

Producing Formation Arb. LKC. Topeka Depth to Top 3,256' Bottom 3,625' T.D. 3,625'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Topeka	Oil	3256	3262	8 5/8	200	None
LKC	Oil	3340	3540	5 1/2	3587	None
Arbuckle	Oil	3585	3625			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set

Ran tubing to 3,150' spotted 80 sxs plug w/ 350 #'s hulls. 2,100' spotted 80 sxs w/150 #'s hulls. 1,200' spotted 60 sxs to surface and squeezed to 500 psi. Squeezed down 8 5/8" and 5 1/2" annulus with 5 sxs to 500 psi.

Name of Plugging Contractor _____ Company _____ License No. _____

Address _____

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: H&B Petroleum Corporation

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

STAN BRADY


(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well, as filed the the same are true and correct, so help me God.

(Signature) Stan Brady

(Address) 309 Kimberly Ct. Clearwater, Kansas

AND SWORN TO before me this 18th day of May, 19 99



Sherilyn Ward
Sherilyn Ward Notary Public

Commission Expires: 5/17/2003

MAY 19 1999
05-19-99
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: 11-5-52

Contractor: Quaker Drilling Co., Inc. Completed: 11-15-52

Crissman No. 3
SW NW NW Sec. 1-13S-18W
Ellis County, Kansas

Elevation: 2085 R.B.

Production: 200 bbls.

Casing Record:

Set 200' of 8 5/8" with
125 sacks cement.

15-057-02820-00-00

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>
Clay and Sand	110	Anhydrite 1312 + 773
Sand, Shale & Shells	200	Heebner 3290 -1205
Shale	405	Lansing 3339 -1254
Sand and Shale	650	Arbuckle 3585 -1500
Shale	950	
Sand	1050	Total Depth 3588 (R)
Red Bed, Sand & Shale	1312	
Anhydrite	1342	
Red Bed & Shale	1400	
Shale & Shells	1690	
Lime & Shale	3588	

I hereby certify that the above is a true and correct copy of
Drillers Log of well drilled in the SW NW NW of Section 1,
Township 13 South, Range 18 West, Ellis County, Kansas.

ALPINE OIL & ROYALTY CO., INC.

By: _____

Subscribed and sworn to before me this _____ day of _____, 195_

Notary Public

My commission expires:
Sept. 14, 1953

RECEIVED
STATE CORPORATION COMMISSION

MAY 19 1953

CONSERVATION DIVISION
Wichita, Kansas