

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-06454-00-02  
Spot: SWNWNE Sec/Twnshp/Rge: 33-13S-14W  
4267 feet from S Section Line, 2398 feet from E Section Line  
Lease Name: BOXBERGER A Well #: 3  
County: RUSSELL Total Vertical Depth: 3481 feet

Operator License No.: 4973  
Op Name: VANTAGE PETROLEUM, INC.  
Address: 562 W STATE RD 4  
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	16	385	0	0
L1	5.5	3330		
PROD	7	3280	0	50 sx

Well Type: SWD UIC Docket No: D14069.0 Date/Time to Plug: 12/10/2010 11:30 AM  
Plug Co. License No.: 32592 Plug Co. Name: WILD WEST WELL SERVICE, INC.  
Proposal Rcvd. from: TOM LARSON Company: VANTAGE PETROLEUM, INC. Phone: (620) 653-7368

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 300# hulls.  
Ordered additional 200 sxs 60/40 pozmix - 4% gel.  
Perf: 200' - 450' - could not get down below 602'.  
Milled and drilled with drill collars for one and 3/4 day.  
Iron in the well - possible packer.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/10/2010 4:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 600' - pumped 100 sxs cement - 3% c.c. water - followed with 100 sxs cement.  
Shut down for 15 minutes - pumped 50 sxs cement with 300# hulls - cement circulated out  
backside.  
POOH. Hooked to casing and pumped 10 sxs cement.  
Max. P.S.I. 500#. S.I.P. 500#.  
Hooked to 7" Braden head - pumped 100 sxs cement - cement circulated out 16" casing valve.

Perfs:

Top	Bot	Thru	Comments
2425	2488		Tarko
675	696		Cedar Hills

Remarks: QUALITY OILWELL CEMENTING COMPANY-TICKET #4469.

Plugged through: TBG

RECEIVED

DEC 21 2010

KCC WICHITA

District: 04

Signed

Ray A Dinkel

(TECHNICIAN)

CM

Form CP-2/3

DEC 16 2010