

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-06455-00-00  
Spot: SEWNWE Sec/Twnshp/Rge: 33-13S-14W  
4290 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: BOXBERGER H Well #: 4  
County: RUSSELL Total Vertical Depth: 3296 feet

Operator License No.: 4973  
Op Name: VANTAGE PETROLEUM, INC.  
Address: 562 W STATE RD 4  
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	16	400	0	w/unknown sxs cmt
PROD	7	3283	0	75 sxs

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/08/2010 11:00 AM  
Plug Co. License No.: 32592 Plug Co. Name: WILD WEST WELL SERVICE, INC.  
Proposal Rcvd. from: TOM LARSON Company: VANTAGE PETROLEUM, INC. Phone: (785) 445-2888

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 500# hulls - 10 sxs gel.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/08/2010 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfed at 1600' - 900'.  
Ran tubing to 3100' - pumped 10 sxs gel - followed with 50 sxs cement and 200# hulls.  
Pulled tubing to 1600' - pumped 100 sxs cement with 100# hulls.  
Pulled tubing to 865' - circulated cement to surface with 75 sxs cement.  
Pulled tubing.  
12/09/2010 - topped off with 20 sxs cement.  
Backside squeezed full of cement.

Perfs:

Top	Bot	Thru	Comments
3292	3296		

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

RECEIVED  
DEC 17 2010

Form CP-2/3

KCC WICHITA

DEC 15 2010