

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-19376-00-00  
Spot: NWNWNE Sec/Twnshp/Rge: 33-13S-14W  
4950 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: H. BOXBERGER "A" Well #: 1  
County: RUSSELL Total Vertical Depth: 3291 feet

Operator License No.: 49737  
Op Name: VANTAGE PETROLEUM, INC.  
Address: 562 W STATE RD 4  
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	15.5	326	0	w/unknown sxs cmt
L1	5.5	3242	0	w/150 sxs cmt
PROD	7	3282	0	w/100 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/07/2010 11:30 AM  
Plug Co. License No.: 32592 Plug Co. Name: WILD WEST WELL SERVICE, INC.  
Proposal Rcvd. from: BRAIN CABLE Company: VANTAGE PETROLEUM, INC. Phone: (785) 445-8222

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 4% gel - 300# hulls - 10 sxs gel.  
Perf: 200' - 900' - 1600'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/07/2010 3:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3200' - pumped 10 sxs gel - followed with 50 sxs cement with 150# hulls.  
Pulled tubing to 1500' - pumped 100 sxs cement with 150# hulls.  
Pulled tubing to 600' - pumped 60 sxs cement - cement circulated to surface.  
POOH. Hooked to casing - pumped 25 sxs cement - circulated out the Braden head.  
Max. P.S.I. 150#.

Perfs:

Top	Bot	Thru	Comments
3282	3291		

Remarks: QUALITY OILWELL CEMENTING COMPANY-TICKET #4489.

Plugged through: TBG

District: 04

Signed Ray A Dinkel  
(TECHNICIAN)

em

Form CP-2/3

DEC 16 2010

RECEIVED  
DEC 21 2010  
KCC WICHITA