

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-21275-00-00
Spot: S2NENENW Sec/Twnshp/Rge: 13-11S-22W
4840 feet from S Section Line, 2970 feet from E Section Line
Lease Name: PYNE Well #: 1
County: TREGO Total Vertical Depth: 3885 feet

Operator License No.: f46567
Op Name: DAVIS PETROLEUM, INC.
Address: 7 SW 26 AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	285	0	200 SX
PROD	5.5	3883	0	200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/21/2010 9:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: MIKE Company: DAVIS PETROLEUM, INC. Phone: (620) 793-3051

Proposed Plugging Method: Ordered 550 sxs 60/40 pozmix - 4% gel - 700# hulls.
Perf: 1770' - 930' - 275'.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/21/2010 1:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3843' - pumped 200 sxs cement with 350# hulls.
Pulled tubing to 1800' - pumped 100 sxs cement with 300# hulls.
Pulled tubing to 800' - pumped 70 sxs cement - cement circulated out the backside.
POOH. Hooked onto casing and pumped 10 sxs cement.
Max. P.S.I. 300#. S.I.P. 300#.
Pulled the bull plug out of Braden head - full of cement.

Perfs:

Top	Bot	Thru	Comments
3804	3808		
3790	3794		

Remarks: ALLIED CEMENTING COMPANY-TICKET #38630.

Plugged through: TBG

District: 04

Signed

Ray A Dinkel

(TECHNICIAN)

CM

RECEIVED
DEC 27 2010

Form CP-2/3

KCC WICHITA

DEC 21 2010