

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21662-00-00
Spot: SESENW Sec/Twnshp/Rge: 9-19S-6W
2310 feet from N Section Line, 2310 feet from W Section Line
Lease Name: OLANDER Well #: 5
County: RICE Total Vertical Depth: 3150 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 1321 W 93 N PO BOX 360
VALLEY CENTER, KS 67147

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	208		130 SX
PROD	4.5	3121		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/07/2010 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE INC Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 12/08/2010 11:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CASING HAS PARTED AT 100-140'. RUN TUBING TO 3000' AND PUMP 35 SX'S COMMON CEMENT WITH CALCIUM AND COTTON HULLS. PULL TUBING TO JUST ABOVE 900'. RUN SLIM GUN DOWN TO 900' AND PERFORATE. PULL SLIM GUN OUT AND PUMP 35 SX'S COMMON CEMENT. PULL TUBING TO 550'. LET SET FOR A WHILE-DID NOT TAG @ 900'. RUN TUBING BACK DOWN TO 900' AND PUMP 35 MORE SX'S CEMENT. PULL TUBING OUT. LET SET OVERNIGHT. TAGGED CEMENT ON 12-8-2010 @ 415'. PERFORATED @ 300' AND RUN TUBING BACK DOWN TO 300' AND CIRCULATED CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3050	3054	CSG	LKC

RECEIVED
DEC 14 2010
12-14-10
KCC WICHITA

Remarks: COPELAND TICKET C-37406

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)