

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22583-00-00
Spot: W2NWNE Sec/Twnshp/Rge: 29-16S-13W
660 feet from N Section Line, 2310 feet from E Section Line
Lease Name: REDETZKE Well #: 1
County: BARTON Total Vertical Depth: 3407 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 1321 W 93 N PO BOX 360
VALLEY CENTER, KS 67147

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	300	0	180 SX
PROD	4.5	3404	0	125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/09/2010 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: STEVE BODINE Company: DAYSTAR PETROLEUM, INC. Phone: (620) 793-2757

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 400# hulls - 7 sxs gel.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/09/2010 1:30 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfed at 1500' - 825'.
Ran tubing to 3347' - pumped 7 sxs gel - followed with 60 sxs cement with 200# hulls.
Pulled tubing to 1500' - pumped 50 sxs cement with 100# hulls.
Pulled tubing to 900' - pumped 35 sxs cement - lost circulation.
Pulled tubing to 600' - pumped 50 sxs cement.
Pulled tubing to 300' - pumped 20 sxs cement - pulled tubing had cement to surface on casing.
Topped off with 20 sxs cement.
Backside pressured up with 10 sxs to 300# P.S.I.

Perfs:

Top	Bot	Thru	Comments
3244	3246		LKC
3196	3202		LKC

RECEIVED
DEC 17 2010

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #37408.

KCC WICHITA

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM

DEC 15 2010