

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-063-20417-00-00  
Spot: SWNESW Sec/Twnshp/Rge: 21-15S-26W  
1650 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: R CHENEY Well #: 3  
County: GOVE Total Vertical Depth: 4298 feet

Operator License No.: 5011  
Op Name: VIKING RESOURCES, INC  
Address: 105 S BROADWAY STE 730  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	305	0	175 SX
PROD	4.5	4290	0	750 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/01/2010 9:00 AM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC  
Proposal Rcvd. from: SHAWN DEVLIN Company: VIKING RESOURCES, INC. Phone: (316) 262-2502

Proposed Plugging Method: Ordered 425 sxs 60/40 pozmix - 4% gel - 600# hulls.  
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/01/2010 1:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 305' w/175 sxs cement.  
4 1/2" production casing set at 4290' w/200 sxs cement.  
DV Tool at 1800' w/500 sxs. TD 4299'. Open hole completion from 4290' - 4298'.  
Production casing had holes.  
Casing filled up to 2500' - ran tubing to 2470' - pumped 100 sxs cement mixed with 200# hulls.  
Pulled tubing to 1000' - pumped 100 sxs cement mixed with 200# hulls.  
Pulled tubing to 500' - pumped 175 sxs cement mixed with 200# hulls.  
Cement to surface. Pulled tubing to surface.  
Connected to 8 5/8" surface casing - pumped 1/10th sack cement.  
Max. P.S.I. 500#. S.I.P. 500#.  
Connected to 4 1/2" production casing - pumped 25 sxs cement.  
Note: Fritzler roustabout observed top of cement in surface casing.  
Casing cut off below plow depth. Cellar closed and leveled.

Perfs:

Top	Bot	Thru	Comments
100	150		OPEN HOLE

Remarks: SWIFT SERVICES CEMENT COMPANY-TICKET #19865.

Plugged through: TBG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

RECEIVED  
DEC 27 2010  
KCC WICHITA

CM

Form CP-2/3

DEC 15 2010