

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-20578-00-00
Spot: NENENW Sec/Twnshp/Rge: 35-21S-4E
4960 feet from S Section Line, 2989 feet from E Section Line
Lease Name: SVITAK Well #: 1
County: MARION Total Vertical Depth: 2341 feet

Operator License No.: 5192
Op Name: SHAWMAR OIL & GAS CO., INC.
Address: 1116 E MAIN PO BOX 9
MARION, KS 66861

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	210		125 SX CMT
PROD	4.5	2338	1500	75 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/06/2011 9:00 AM
Plug Co. License No.: 5192 Plug Co. Name: SHAWMAR OIL & GAS CO., INC.
Proposal Rcvd. from: BEAU CLOUTIER Company: _____ Phone: (620) 382-2932

Proposed Plugging Method: As per KCC regulations.

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/06/2011 2:15 PM KCC Agent: SHANE JONES

Actual Plugging Report:

SHAWMAR DROPPED SAND TO PLUG OFF BOTTOM. THEY TAGGED SAND @ 2220' AND CAPPED W/4SX. DYNA-LOG SHOT OFF CASING 2 1500'. CASING FREE. SHAWMAR LAID OUT CASING AND RAN 2" TUBING TO 258'. 1/6/11 WAITING ON CONSOLIDATED HUNG UP ON ANOTHER JOB. CONSOLIDATED ARRIVED @12:30 PM. THEY TIED ON TO TUBING AND BROKE CIRCULATION WITH WATER. CONSOLIDATED SWITCHED TO CEMENT AND CIRCULATED IT TO SURFACE. SHAWMAR PULLED TUBING. CEMENT HOLDING @ ABOUT 1' DOWN INSIDE CASING. CONSOLIDATED USED 80 SXS 60/40 POS W/4% GEL TK #30881. 1/11/11 I CHECKED TOP PLUG FINDING IT DOWN APPROX 8'. OPERATOR WILL CUT OFF CASING AND TOP OFF WELL.

Perfs:

Top	Bot	Thru	Comments
2278	2288	CSG	Mississippian

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 25 2011
CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)