

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-20767-00-01
Spot: NESENW Sec/Twnshp/Rge: 35-21S-4E
3634 feet from S Section Line, 3046 feet from E Section Line
Lease Name: SVITAK Well #: 2
County: MARION Total Vertical Depth: 2381 feet

Operator License No.: 5192
Op Name: SHAWMAR OIL & GAS CO., INC.
Address: 1116 E MAIN PO BOX 9
MARION, KS 66861

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8	200		125 SX
T1	2.875	2284		
PKR		2284		
PROD	4.5	2379	1300	75 SX

Well Type: SWD UIC Docket No: D28603.0 Date/Time to Plug: 01/06/2011 9:00 AM
Plug Co. License No.: 5192 Plug Co. Name: SHAWMAR OIL & GAS CO., INC.
Proposal Rcvd. from: BENNY KEY Company: Phone: (620) 382-2932

Proposed Plugging Method: AS PER KCC REGULATIONS.

Plugging Proposal Received By: Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/06/2011 4:00 PM KCC Agent: SHANE JONES

Actual Plugging Report:

SHAWMAR DROPPED SAND TO PLUG OFF BOTTOM. THEY TAGGED SAND @ 2245' AND CAPPED W/4 SX. DYNA-LOG SHOT OFF CASING @ 1300'. CASING FREE. 1/6/11 SHAWMAR MOVED OVER FROM SVITAK #1 AND RIGGED UP. THEY RAN 2" TUBING TO 258'. CONSOLIDATED TIED ON TO TUBING AND BROKE CIRCULATION WITH WATER. CONSOLIDATED SWITCHED TO CEMENT AND CIRCULATED IT TO SURFACE. SHAWMAR PULLED TUBING. CEMENT DOWN ABOUT 30' INSIDE CASING. CONSOLIDATED TOPPED OFF CASING. THEY USED 120 SXS 60/40 POS W/4% GEL TK #30882. 1/11/11 I CHECKED TOP PLUG FINDING IT DOWN APPROX 40'. OPERATOR WILL CUT OFF CASING AND TOP OFF WELL.

Perfs:

Top	Bot	Thru	Comments
2314	2324	CSG	MISSISSIPPI


RECEIVED
KANSAS CORPORATION COMMISSION
JAN 25 2011
CONSERVATION DIVISION
WICHITA, KS

Remarks: PBTD 2369', PLUGGED DUE TO FAILED MIT AND NOT WORTH FIXING.

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)