

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-037-21419-00-00
Spot: SWNESW Sec/Twnshp/Rge: 33-28S-22E
1650 feet from S Section Line, 3630 feet from E Section Line
Lease Name: WALSH Well #: 8
County: CRAWFORD Total Vertical Depth: 420 feet

Operator License No.: 6766
Op Name: N & W ENTERPRISES, INC.
Address: 1111 S MARGRAVE
FORT SCOTT, KS 66701

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF | | 20 | | |
| PROD | 2.875 | 416 | | 35 SX |

Well Type: EOR UIC Docket No: E25253.9 Date/Time to Plug:
Plug Co. License No.: 6766 Plug Co. Name: N & W ENTERPRISES, INC.
Proposal Rcvd. from: N & W ENTERPRISES Company: Phone: (620) 223-6559

Proposed Plugging Method: RUN 1 INCH INSIDE 2 7/8 TO 410 FEET DEPTH. WASH WELL OUT WITH WATER. CIRCULATE CEMENT TO TOP OF WELL. PULL ONE INCH OUT OF WELL. HOOK ON TO WELL AND PRESSURIZE WELL TO 150 LBS. WITH CEMENT AND SHUT IN WELL. AFTER THE CEMENT CURES WELL WILL BE CUT OFF 4 FEET BELOW GROUND LEVEL.

Plugging Proposal Received By: WitnessType: NONE
Date/Time Plugging Completed: 08/03/2010 12:00 AM KCC Agent: RUSSELL HINE

Actual Plugging Report:

Perfs:

Ran 1" cement string inside of 2-7/8" to 410' and circulated cement to surface. 1" was pulled and well was topped off, then hooked to 2-7/8" and pumped cement and shut in at 150psi. Well was cut off and buried.

RECEIVED

JAN 6 2011 RH

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed

Russell Hine

(TECHNICIAN)

RECEIVED

JAN 10 2011

Form CP-2/3

KCC WICHITA