

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-037-01486-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 33-28S-22E
1650 feet from S Section Line, 2310 feet from E Section Line
Lease Name: MEYER INJ Well #: OLD 88
County: CRAWFORD Total Vertical Depth: 405⁷ feet

Operator License No.: 6766
Op Name: N & W ENTERPRISES, INC.
Address: 1111 S MARGRAVE
FORT SCOTT, KS 66701

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD 2		390		3 SX

Well Type: EOR UIC Docket No: _____ Date/Time to Plug: 07/26/2010 8:00 AM
Plug Co. License No.: 6766 Plug Co. Name: N & W ENTERPRISES, INC.
Proposal Rcvd. from: THOMAS L. NORRIS Company: _____ Phone: (620) 223-6559

Proposed Plugging Method: 2 INCH PIPE HAS CEMENT INSIDE TO THE TOP. OUTSIDE OF 2 INCH PIPE THERE IS NO CEMENT. WASH 1 INCH PIPE OF OUTSIDE OF 2 INCH PIPE IN WELL BORE TO 350 FEET DEEP. CIRCULATE CEMENT FROM 350 FEET TO TOP. REMOVE 1 INCH AND CUT OFF CASING 4 FEET BELOW GROUND LEVEL.

Plugging Proposal Received By: RUSSELL HINE WitnessType: NONE
Date/Time Plugging Completed: 08/03/2010 12:00 AM KCC Agent: RUSSELL HINE

Actual Plugging Report:

Perfs:

Ran cement string to 405 on outside of 2" and circulated cement to surface. Pulled 1" and topped off well. Cut off casing and pipe and buried.

RECEIVED

JAN 6 2011 RH

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed Russell Hine
(TECHNICIAN)

RECEIVED Form CP-2/3

JAN 10 2011

KCC WICHITA