

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-11443-00-00
Spot: NWSENESE Sec/Twnshp/Rge: 1-31S-2W
1842 feet from S Section Line, 337 feet from E Section Line
Lease Name: ANSON WEST UNIT B Well #: 7-02
County: SUMNER Total Vertical Depth: 3741 feet

Operator License No.: 33190
Op Name: NOBLE ENERGY, INC.
Address: 1625 BROADWAY, STE 2200
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	424		300 SX
PROD	5.5	3729		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/24/2010 8:00 AM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: GERALDINE HOLINDE Company: NOBLE ENERGY INC Phone: (785) 639-6302

Proposed Plugging Method: AS PER KCC RULES & REGS / 35 SXS @ 3700', REC. CASING, CIRCULATE CEMENT @ 475'-0'

Plugging Proposal Received By: STEVE VANGIESON Witness Type: NONE
Date/Time Plugging Completed: 11/29/2010 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 3700', BASIC CEMENTING ESTABLISHED CIRCULATION AND PUMPED 100# HULLS & 35 SXS CLASS A COMMON 3% CC AND DISPLACED IN CASING. PRESSURED CASING, HELD OK. PERFORATED SQUEEZE HOLES @ 440', 11-29-2010, RIH W/TBG @ 435', BASIC CEMENTING ESTABLISHED CIRCULATION, MIXED & PUMPED 150 SXS CLASS A COMMON CEMENT TO SURFACE. CEMENT CIRCULATED. LAYED TBG DOWN, TOPPED WELL BACK TO SURFACE CEMENT. PLUG DOWN 11-29-2010, 5:00 PM. BASIC CEMENTING TICKET #3208. 12-7-2010, TAGGED CEMENT @ 15'. DUMPED 1/2 YD SLURRY MIX. <10% SAND BACK TO SURFACE. CUT OFF CASING & WELDED CAP ON TOP.

Perfs:

Top	Bot	Thru	Comments
3729	3741	OH	

RECEIVED
DEC 14 2010
KCC WICHITA

Remarks: 300' TOP SALT, 100' THICKNESS

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)