

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-30173-00-00
Spot: NENW Sec/Twnshp/Rge: 31-30S-1W
4285 feet from S Section Line, 3307 feet from E Section Line
Lease Name: BATES UNIT B Well #: 1-03
County: SUMNER Total Vertical Depth: 3751 feet

Operator License No.: 33190
Op Name: NOBLE ENERGY, INC.
Address: 1625 BROADWAY, STE 2200
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	438		
PROD	3733	6		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/24/2010 5:00 PM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: GERALD HOLINDE Company: NOBLE ENERGY INC Phone: (785) 639-6302

Proposed Plugging Method: AS PER KCC RULES & REGS / 35 SXS @ 2830', REC. CASING, CIRCULATE CEMENT @ 440'-0'

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 11/24/2010 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W / TBG @ 2812', BASIC CEMENTING ESTABLISHED CIRCULATION AND PUMPED 100# HULLS & 35 SXS CLASS A COMMON 3% CC AND DISPLACED IN CASING. PRESSURED CASING, HELD OK. 11-24-2010, PERFORATED SQUEEZE HOLES & 440', RIH W/TBG @ 440', BASIC CEMENTING ESTABLISHED CIRCULATION, MIXED & PUMPED 150 SXS CLASS A COMMON CEMENT TO SURFACE. CEMENT CIRCULATED. LAYED TBG DOWN, TOPPED WELL BACK TO SURFACE W/CEMENT. PLUG DOWN 11-24-2010, 5:00 PM. BASIC CEMENTING TICKET #3207. 12-7-2010, TAGGED CEMENT @123'. DUMPED 3-1/2 YRDS SLURRY MIX, <10% SAND BACK TO SURFACE. CUT OFF CASING & WELDED CAP ON TOP.

Perfs:

Top	Bot	Thru	Comments
3733	3751	OH	

RECEIVED
DEC 14 2010
KCC WICHITA

Remarks: 300' TOP SALT, 100' THICKNESS / CASING LEAK @ 2830'

Plugged through: TBG

District: 02

Signed *Duane Krueger*
(TECHNICIAN)