

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-20005-00-01
Spot: SWSENE Sec/Twnshp/Rge: 36-30S-2W
2953 feet from S Section Line, 692 feet from E Section Line
Lease Name: BATES UNIT Well #: 5-1
County: SUMNER Total Vertical Depth: 4185 feet

Operator License No.: 33190
Op Name: NOBLE ENERGY, INC.
Address: 1625 BROADWAY, STE 2200
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	437		300 SX
PROD	5.5	3798		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/22/2010 8:00 AM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: GERALDINE HOLINDE Company: NOBLE ENERGY INC Phone: (785) 639-6302

Proposed Plugging Method: AS PER KCC RULES & REGS/35 SXS @ 3150', REC. CASING, CIRCULATE CEMENT @ 487'-0'

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 11/24/2010 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 3150', BASIC CEMENTING ESTABLISHED CIRCULATION AND PUMPED 100# HULLS & 35 SXS CLASS A COMMON 3% CC AND DISPLACED IN CASING. PRESSURED CASING, HELD OK. 11-24-2010, PERFORATED SQUEEZE HOLES @ 440', RIH W/TBG @ 440', BASIC CEMENTING ESTABLISHED CIRCULATION, MIXED & PUMPED 150 SXS CLASS A COMMON CEMENT TO SURFACE. CEMENT CIRCULATED. LAYED TBG DOWN, TOPPED WELL BACK TO SURFACE W/CEMENT. PLUG DOWN 11-24-2010, 5:00 PM. BASIC CEMENTING TICKET #3206. 12-7-2010, TAGGED CEMENT @54'. DUMPED 1-1/2 YDS SLURRY MIX. <10% SAND BACK TO SURFACE. CUT OFF CASING & WELDED CAP ON TOP.

Perfs:

Top	Bot	Thru	Comments
3194	3200	CSG	SQUEEZED - REPE
3172	3176	CSG	SPF
3142	3153	CSG	SPF
3086	3200	CSG	SPF

RECEIVED
DEC 14 2010
KCC WICHITA

Remarks: 300' TOP SALT, 100' THICKNESS

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)