

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21643-00-00
Spot: NENESWSE Sec/Twnshp/Rge: 24-33S-6W
1220 feet from S Section Line, 1551 feet from E Section Line
Lease Name: ALBINA E. WOLFF TRUST Well #: 1-24
County: HARPER Total Vertical Depth: 4600 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	263		190 SX CMT
T1	2.375	3527		
PROD	4.5	3659	2850	100 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/22/2010 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3409

Proposed Plugging Method: SAND TO 3470 AND 4 SKS, RECOVER CASING, 35 SKS 1000, 35 SKS 650, CIRC CMT 310-0

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 12/22/2010 3:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 3480' AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS PULLED TO 1000', WHERE 35 SK OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 650', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 315R', WHERE CMT WAS CIRCULATED TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
3533	3535		STALNAKER
3529	3531		

Remarks: QWS 60/40 4% GEL

Plugged through: CSG

District: 02

Signed _____



(TECHNICIAN)

RECEIVED

JAN 03 2011

Form CP-2/3

KCC WICHITA

✓