

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-20164-00-00
Spot: NE Sec/Twnshp/Rge: 24-24S-41W
1315 feet from N Section Line, 1375 feet from E Section Line
Lease Name: PLUMMER JEANNETTE Well #: 1
County: HAMILTON Total Vertical Depth: 2400 feet

Operator License No.: 9687
Op Name: SMITH, WANDA
Address: 401 BARTON PO BOX 375
SYRACUSE, KS 67878

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	380		WITH 300 SX CMT
PROD	4.5	2399	0	WITH 500 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/30/2010 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: GARLAND SMITH Company: WANDA SMITH Phone: (620) 384-5277

Proposed Plugging Method: LOAD HOLE & RUN BOND LOG TO DETERMINED TOC. PERFORATE AS REQUIRED. RUN TBG TO BOTTOM & SPOT PLUGS AS REQUIRED.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/30/2010 12:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:


**3 JOINTS TBG LEFT IN HOLE. TOP OF FISH @ 2294'* CHECK FLUID LEVEL @ 1400'. LOAD & TEST CASING TO 500#. INJECTION RATE 1 1/2 BPM @ 400# AFTER 900# BREAKDOWN. PUMP 50 SX CMT & 200# HULLS AT 2332'. PUMP 10 BBL SPACER AT 1530'. PUMP 50 SX CMT AT 900'-0'. PRESSURE CASING TO 500#. HOLDING AT 300#. PUMP 10 SX CMT DOWN ANNULUS TO 300#. HOLDING AT 200#.

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED
DEC - 8 2010
KCC DODGE CITY

RECEIVED
DEC 27 2010
KCC WICHITA

Form CP-273