

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-21604-00-00  
Spot: NWSWSW Sec/Twnshp/Rge: 26-27S-18W  
1000 feet from S Section Line, 339 feet from W Section Line  
Lease Name: IKERD Well #: 1  
County: KIOWA Total Vertical Depth: 4939 feet

Operator License No.: 6743  
Op Name: SOUTHWIND PETROLEUM CORP.  
Address: 1400 W 14TH ST  
WICHITA, KS 67203

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	349		WITH 275 SX CMT
PROD	5.5	4930	3020	WITH 210 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/15/2010 1:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/15/2010 2:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SAND BACK TO 4590' & PUT 5 SX CMT ON TOP OF SAND BRIDGE. 1ST PLUG AT 1150' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 380' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4760	4784		
4674	4680		
4652	4655		
4640	4646		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

RECEIVED  
DEC 23 2010  
KCC DODGE CITY

Signed Stephen J. Pfeifer  
(TECHNICIAN)

RECEIVED  
JAN 06 2011  
KCC WICHITA

Form CR-2/R