

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-003-21356-00-00

Spot: NENENESW

Sec/Twnshp/Rge: 16-22S-19E

2453 feet from S Section Line, 2842 feet from E Section Line

Lease Name: BOOTS

Well #: 1

County: ANDERSON

Total Vertical Depth: 861 feet

Operator License No.: 33097

Op Name: SOUTHERN STAR CENTRAL GAS PIPE

Address: 4700 HWY 56

OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	6.25	22		NO SXS LISTED
PROD	2.5	861		NO SXS LISTED

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 10/05/2010 10:00 AM

Plug Co. License No.: 34059

Plug Co. Name: HURRICANE SERVICES, INC.

Proposal Rcvd. from: STEVE BENJAMIN

Company:

Phone: (785) 448-4804

Proposed Plugging Method: TIE TO 2/12" - ESTABLISH FLOW RATE & SQUEEZE CEMENT INTO FORMATION UNTIL DESIRED AMOUNT OF CEMENT AND PRESSURE IS ACHIEVED, FILLING WELL TO SURFACE. CUT OFF PIPE 3 FT. BELOW SURFACE, CUT, CAP AND BACKFILL.

Plugging Proposal Received By:

WitnessType: NONE

Date/Time Plugging Completed 10/05/2010 11:00 AM

KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 1-INCH PIPE IN 2-INCH PIPE AND PUMP CEMENT FROM TD (861 FEET) TO SURFACE. PULL PIPE THEN HOOK ON TO 2-INCH AND SQUEEZE CEMENT AT 600 PSI. A TOTAL OF 56 SACKS OF CEMENT WERE USED TO PLUG THE WELL.

Perfs:

Top	Bot	Thru	Comments
838	842		

RECEIVED

JAN 12 2011

LS

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed

[Signature]

(TECHNICIAN)

KANSAS CORPORATION COMMISSION
1-18-11
JAN 18 2011
RECEIVED

Form CP-2/3