

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-02459-00-00
Spot: W2NESE Sec/Twnshp/Rge: 11-12S-18W
1980 feet from S Section Line, 990 feet from E Section Line
Lease Name: COLORADO-KOERNER Well #: 1
County: ELLIS Total Vertical Depth: 3641 feet

Operator License No.: 30553
Op Name: UNREIN, GLENN DBA UNREIN OIL CO
Address: 300 W 40TH ST
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1378	0	450 SX
PROD	5.5	3639	0	100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/30/2010 9:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: STEVEN THOMASON Company: UNREIN OIL COMPANY Phone: (785) 628-6231

Proposed Plugging Method:
1st. Ordered out 550 sxs 60/40 pozmix - 4% gel - 13 sxs gel spacer - 500# hulls.
2nd. Ordered out 200 sxs additional 60/40 pozmix - 4% gel.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/30/2010 4:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated two holes at 1350'.
Ran tubing to 3450'. Tagged junk in the hole.
Pulled up to 3360'.
Quality Oil Well Cementing pumped 13 sxs gel spacer - followed with 50 sxs cement.
Pulled tubing to 1605'.
Quality Oil Well Cementing pumped 175 sxs cement with 350# hulls - circulated cement out of 5 1/2" casing.
PTOH. Quality Oil Well Cementing pumped 325 sxs cement down 5 1/2" casing to circulate cement out of 8 5/8".
Ran out of cement - waited 1.5 hours.
Quality Oil Well Cementing pumped 200 sxs cement down 5 1/2" casing - good circulation out 8 5/8" - no cement. Shut in.
01/05/2011 - Operator cut 5 1/2" casing and 8 5/8" off - ran wireline - cement at 200' - both 5 1/2" and 8 5/8".
01/19/2011 - Checked by Pat Staab. Operator topped 5 1/2" and 8 5/8" off with 1.5 yards Redi-Mix - no aggregate.
01/21/2011 - Checked by Pat Staab. Operator topped 5 1/2" and 8 5/8" off with 2 yards Redi-Mix. The hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3639	3641		Open hole ar buckle
3465	3470		LANSING KC
3442	3447		LANSING KC
3418	3423		LANSING KC
3403	3408		LANSING KC

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

CM

Form CP-2/3

JAN 21 2011

RECEIVED
JAN 26 2011
KCC WICHITA