

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20768-00-01
Spot: SWNWSW Sec/Twnshp/Rge: 28-1S-35W
1894 feet from S Section Line, 4741 feet from E Section Line
Lease Name: SABATKA Well #: 1
County: RAWLINS Total Vertical Depth: 4395 feet

Operator License No.: 5046
Op Name: RAYMOND OIL COMPANY, INC.
Address: PO BOX 48788
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	305	0	170 SX
PROD	4.5	4365	0	150 SX

Well Type: EOR UIC Docket No: E26788.1 Date/Time to Plug: 10/29/2010 9:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: ART SCHOENHOEFER Company: RAYMOND OIL COMPANY, INC. Phone: (316) 267-4214

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 600# hulls.
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/29/2010 11:30 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 305' w/170 sxs cement.
4 1/2" production casing set at 4365' w/150 sxs cement.
4 1/2" casing perforated at 3135' and 2440'.
Ran tubing to 3100' - pumped 175 sxs cement mixed with 450# hulls.
Pulled tubing to 1550' - pumped 175 sxs cement with 200# hulls - cement circulated to surface.
Pulled tubing to surface.
Connected to 8 5/8" surface casing - pumped 50 sxs cement.
Cement 6 seconds from surface in 4 1/2" casing.
11/22/2010 - Topped 4 1/2" casing with 2 1/4 yards neat cement.

Perfs:

Top	Bot	Thru	Comments
4292	4302		
4238	4242		

Remarks: CONSOLIDATED CEMENT SERVICES.

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

NOV 30 2010

RECEIVED
DEC 27 2010
KCC WICHITA

Form CP-2/3