

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-20301-00-00
Spot: SENESESW Sec/Twnshp/Rge: 34-25S-31W
2166 feet from S Section Line, 2730 feet from E Section Line
Lease Name: MINTER-WILSON Well #: 1
County: FINNEY Total Vertical Depth: 2670 feet

Operator License No.: 33358
Op Name: RENICK ENERGY, L.C.
Address: 10502 6 RD
INGALLS, KS 67853

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	577		WITH 150 SX CMT
PROD	5.5	2669	1000	WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/08/2010 11:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PLUG AT 1000' WITH 75 SX CMT. PLUG AT 590' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT
Date/Time Plugging Completed: 12/08/2010 3:30 PM

Witness Type: COMPLETE (100%)
KCC Agent: KEN JEHLIK

Actual Plugging Report:

TBG SANDED IN THE HOLE DUE TO GLORIETTA CASING LEAK. TOP OF FISH 1400'. RAN 1 1/2" TBG TO 1370' & SPOTTED 100# HULLS & 25 SX CMT. LET SET. TAG @ 1300'. PULL 5 1/2" CASING OUT & RUN 1 1/2" TBG TO 1000'. CIRCULATE HOLE WITH MUD & SPOT 150# HULLS @ 1000'. WAIT 30 MINUTES. PLUG AT 1000' WITH 75 SX CMT. PLUG AT 570' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2622	2630		

RECEIVED
DEC 30 2010
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: TBG

District: 01

Signed _____

Ken Jehlik
(TECHNICIAN)

RECEIVED
DEC 22 2010

KCC DODGE CITY

Form CP-23