

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-01668-00-00
Spot: SWNWNWNW Sec/Twnshp/Rge: 6-18S-10W
4912 feet from S Section Line, 5067 feet from E Section Line
Lease Name: AMES W R Well #: 1
County: RICE Total Vertical Depth: 3244 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	16	140		150 SX
PROD	8.625	3235		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/01/2010 8:00 AM
Plug Co. License No.: 31528 Plug Co. Name: MIKE KELSO OIL, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE KELSO OIL INC Phone: (620) 793-2525

Proposed Plugging Method: KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 09/03/2010 3:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

RAN TUBING INTO 2650' SPOTTED 40 BBLs MUD MIX AND 100 SX OF CEMENT WITH 400# OF HULLS. PULLED UP TO 1250' SPOTTED 100 SX CEMENT WITH 3% CC COULD NOT TAG CEMENT, RAN ANOTHER 75 SX OF CEMENT AND 300# OF HULLS LET SET OVERNIGHT -- 9/3/10 TAGGED CEMENT AT 900', SPOTTED 50 SX OF CEMENT, PULLED UP TO 250' CIRCULATED WITH 80 SX OF CEMENT INSIDE CASING AND 160 SX OF CEMENT ON BACKSIDE FILLING ANNULUS.

Perfs:

Top	Bot	Thru	Comments
3235	3244	CSG	ARBUCKLE OPEN

Remarks: COPELAND CEMENT OUT OF GREAT BEND, NATHAN -- TICKET #35100

Plugged through: TBG

District: 02

Signed

B. J. Hope

(TECHNICIAN)

RECEIVED

DEC 15 2010 ^{am} CP-2/3

KCC WICHITA

✓