

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-21127-00-01
Spot: SWNENENE Sec/Twnshp/Rge: 8-15S-29W
4856 feet from S Section Line, 353 feet from E Section Line
Lease Name: BURNETT Well #: 1
County: GOVE Total Vertical Depth: 4350 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	256		160 SX
PROD	4.5	2008		450 SX

Well Type: SWD UIC Docket No: D25157.0 Date/Time to Plug: 12/02/2010 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: GARY ROWE Company: Phone: (620) 214-0330

Proposed Plugging Method: Order 250 sx 60/40 pozmix w/ 4% gel and 600# hulls.
Plug through tubing:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/07/2010 2:15 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface pipe set @ 256' w/160 sx.
4 1/2" casing set @ 2008' w/450 sx.
Perforations @ 1740' - 1770'
Casing had holes.
Ran tubing to 1687'. Pumped 125 sx cement mixed w/100# hulls.
Pulled tubing to 885'. Pumped 60 sx cement mixed w/ 100# hulls. Cement to surface.
Pulled tubing to surface. Pumped 30 sx cement.
8 5/8" full of cement.
Plug complete.

Perfs:

Top	Bot	Thru	Comments
1740	1770		CEDAR HILLS

RECEIVED
DEC 17 2010
KCC WICHITA

Remarks: ALLIED TICKET # 33,468. GPS LAT 38.77112, LONG -100.56005

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM