

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-04151-00-00  
Spot: SWNWNW Sec/Twnshp/Rge: 22-17S-14W  
4290 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: EVERLEIGH Well #: 2  
County: BARTON Total Vertical Depth: 3358 feet

Operator License No.: 3293  
Op Name: RUSSELL OIL, INC.  
Address: PO BOX 8050  
EDMOND, OK 73083

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	839	0	475 SX
PROD	5.5	3342	0	125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/21/2011 9:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: TODD A. BROWN Company: RUSSELL OIL, INC. Phone: (785) 445-6270

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls - 8 sxs gel.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/21/2011 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Perfed at 1500' - 835' - 200'.  
Ran tubing to 3338' - pumped 8 sxs gel - followed with 50 sxs cement and 200# hulls.  
Pulled tubing to 1535' - pumped 80 sxs cement with 100# hulls.  
Pulled tubing to 847' - circulated cement to surface with 35 sxs cement.  
Pulled tubing - tied to casing and pumped 90 sxs cement - circulated out surface pipe.

Remarks: ALLIED CEMENTING COMPANY-TICKET #38645.

Plugged through: CSG

RECEIVED  
JAN 26 2011  
KCC WICHITA

District: 04

Signed Bruce Rodie  
(TECHNICIAN) CM