

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20789-00-01
Spot: SWNENESE Sec/Twnshp/Rge: 19-16S-7W
1989 feet from S Section Line, 434 feet from E Section Line
Lease Name: FLEMING OWWO Well #: 1-19
County: ELLSWORTH Total Vertical Depth: 1952 feet

Operator License No.: 3882

Op Name: SAMUEL GARY JR. & ASSOCIATES, IN

Address: 1515 WYNKOOP, STE 700
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	290		200 sxs
PROD	4.5	1923	940	150 sxs

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 12/27/2010 12:30 PM

Plug Co. License No.: 31529

Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO

Company: MIKE'S TESTING & SALVAGE INC Phone: (620) 562-8088

Proposed SEE BELOW
Plugging Method:

Plugging Proposal Received By: DUANE KRUEGER

Witness Type: PARTIAL

Date/Time Plugging Completed: 12/27/2010 2:20 PM

KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

MIRU, CK BOTTOM. SAND TO 1860' AND CAP WITH 4 SX'S CEMENT. CUT CASING OFF AT 940' AND PULL TO 900' AND PUMP 35 SX'S CEMENT. PULL CASING TO 600' AND PUMP 35 SX'S CEMENT. PULL CASING TO 340' AND CIRCULATE CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF.

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET #C-37243.

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

RECEIVED

JAN 03 2011

Form CP-2/3

Virgil Clothier

KCC WICHITA