

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-21911-00-00
Spot: S2N2S2SE Sec/Twnshp/Rge: 22-16S-16W
890 feet from S Section Line, 1320 feet from E Section Line
Lease Name: HOSS Well #: 1-22
County: RUSH Total Vertical Depth: 3620 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1515 WYNKOOP, STE 700
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1049		WITH 400 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/05/2010 6:00 PM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: 1ST PLUG AT 3500' WITH 50 SX CMT. 2ND PLUG AT 1080' WITH 50 SX CMT. 3RD PLUG AT 460' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: NONE
Date/Time Plugging Completed: 12/05/2010 9:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

1ST PLUG AT 3500' WITH 50 SX CMT. 2ND PLUG AT 1080' WITH 50 SX CMT. 3RD PLUG AT 460' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: DP

District: 01

Signed

Richard M. Lacey
(TECHNICIAN)

RECEIVED

DEC 15 2010

KCC DODGE CITY

RECEIVED

DEC 20 2010

KCC WICHITA

Form CP-2/3