

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-199-20389-00-00
Spot: NENESW Sec/Twnshp/Rge: 24-12S-38W
2310 feet from S Section Line, 2970 feet from E Section Line
Lease Name: WRIGHT FARMS Well #: 11A-24-1238
County: WALLACE Total Vertical Depth: 5200 feet

Operator License No.: 33476
Op Name: FIML NATURAL RESOURCES, LLC
Address: 410 17TH ST STE 900
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	439		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/15/2011 12:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: GARY Company: FIML NATURAL RESOURCES, LLC Phone: (303) 893-5073

Proposed Plugging Method: Ordered 245 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS WitnessType: NONE
Date/Time Plugging Completed: 01/15/2011 1:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:


1st. Plug at 5090' w/25 sxs.
2nd. Plug at 2285' w/25 sxs.
3rd. Plug at 1640' w/100 sxs.
4th. Plug at 490' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



RECEIVED
KANSAS CORPORATION COMMISSION
1-21-11
JAN 21 2011 Form CP-2/3
CONSERVATION DIVISION
WICHITA, KS

JAN 19 2011