

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-193-20300-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 23-9S-32W
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: OHL ROGGE ET AL Well #: 58-23
County: THOMAS Total Vertical Depth: 4732 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 S ST FRANCIS PO BOX 2757
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	344	0	230 SX
T1	2.375	4338		
PROD	4.5	4731	0	325 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/14/2010 9:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: GARY REH Company: GORE OIL COMPANY Phone: (308) 345-1597

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.
Plug through casing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/14/2010 10:30 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 344' w/230 sxs cement.
4 1/2" production casing set at 4731' w/325 sxs cement.
Multi stage collar at 2570' w/550 sxs cement.
TD 4732'. PBTD 4688'.
Connected to 4 1/2" production casing - pumped 300 sxs cement mixed with 500# hulls.
Max. P.S.I. 250#. S.I.P. 250#.
Connected to 8 5/8" surface casing - pressured to 500# with 1/2 barrel water.

Perfs:

Top	Bot	Thru	Comments
4316	4324		
4280	4287		

Remarks: SWIFT CEMENTING SERVICE-TICEK #19258.

Plugged through: CSG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

RECEIVED

DEC 27 2010

KCC WICHITA

Form CP-2/3

DEC 15 2010