

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-00797-00-00  
Spot: N2SESENE Sec/Twnshp/Rge: 18-7S-20W  
3000 feet from S Section Line, 330 feet from E Section Line  
Lease Name: LESAGE TWIN Well #: 1  
County: ROOKS Total Vertical Depth: 3630 feet

Operator License No.: 33723  
Op Name: PAUL BOWMAN OIL TRUST  
Address: 801 CODELL RD  
CODELL, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	190	0	w/165 sxs cmt
PROD	4.5	3629	0	w/150 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/21/2010 10:30 AM  
Plug Co. License No.: 33868 Plug Co. Name: RENEGADE WELL SERVICE LLC  
Proposal Rcvd. from: DONALD A. BOWMAN Company: PAUL BOWMAN OIL TRUST Phone: (785) 434-2286

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.  
Perfed at 1670' and 1000'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/21/2010 12:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2120' - pumped 175 sxs 60/40 pozmix - 4% gel with 300# hulls.  
Pulled tubing to 1020' - pumped 70 sxs 60/40 pozmix - 4% gel with 200# hulls to circulate to surface.  
Pulled all tubing. Topped off 4 1/2" casing with 10 sxs 60/40 pozmix - 4% gel.  
Hooked to 8 5/8" x 4 1/2" annulus.  
Max. P.S.I. 200#.

Perfs:

Top	Bot	Thru	Comments
3531	3544		MARMINGTON - A
3390	3393		LANSING
3382	3384		LANSING
3348	3350		LANSING

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4725.

KCC WICHITA

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

*Pat Bedore*

(TECHNICIAN)

CM

Form CP-2/3

DEC 23 2010