

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-039-20795-00-02  
Spot: SWNESE Sec/Twnshp/Rge: 10-3S-27W  
1650 feet from S Section Line, 990 feet from E Section Line  
Lease Name: GILLESPIE Well #: 1-10  
County: DECATUR Total Vertical Depth: 3826 feet

Operator License No.: 3602  
Op Name: PHILPOTT OIL & GAS CO INC  
Address: 408 MAIN ST PO BOX 450  
ATWOOD, KS 67730

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	262	0	190 SX
PROD	4.5	3825	0	130 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/09/2010 9:00 AM  
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC  
Proposal Rcvd. from: ROGER PHILPOTT Company: PHILPOTT OIL & GAS CO INC. Phone: (785) 626-3011

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 600# hulls.  
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/14/2010 1:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 262' w/190 sxs cement.  
4 1/2" casing set at 3825' w/130 sxs cement.  
Multi stage collar at 2256' w/450 sxs cement.  
TD 3826'. PBT 3776'.  
Ran tubing to 2520' - pumped 160 sxs cement mixed with 300# hulls.  
Pulled tubing to 1260' - pumped 90 sxs cement mixed with 200# hulls.  
Cement to surface. Pulled tubing to surface.  
Connected to 4 1/2" casing - pumped 20 sxs cement. Cement falling in casing.  
12-14-2010 - Filled 4 1/2" production casing with 20 sxs cement.  
Connected to 8 5/8" surface casing - pumped 20 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3727	3729		LKC
3644	3646		LKC

Remarks: CONSOLIDATED OILWELL SERVICES, LLC-TICKET #30018.

Plugged through: CSG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

RECEIVED  
DEC 27 2010  
KCC WICHITA  
Form CP-2/3

DEC 15 2010