

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-039-20805-00-00  
Spot: NWSENWSE Sec/Twnshp/Rge: 10-3S-27W  
1930 feet from S Section Line, 1880 feet from E Section Line  
Lease Name: GILLESPIE Well #: 4-10  
County: DECATUR Total Vertical Depth: 3840 feet

Operator License No.: 3602  
Op Name: PHILPOTT OIL & GAS CO INC  
Address: 408 MAIN ST PO BOX 450  
ATWOOD, KS 67730

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	253	0	200 SX
PROD	4.5	3839	0	460 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/14/2010 1:30 PM  
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC  
Proposal Rcvd. from: ROGER PHILPOTT Company: PHILPOTT OIL & GAS CO INC. Phone: (785) 626-3011

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 600# hulls.  
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/14/2010 4:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 253' w/200 sxs cement.  
4 1/2" casing set at 3839' w/460 sxs cement.  
TD 3840'. PBTD 3800'.  
Ran tubing to 2520' - pumped 160 sxs cement mixed with 300# hulls.  
Pulled tubing to 1260' - pumped 50 sxs cement mixed with 150# hulls - cement to surface.  
Pulled tubing to surface.  
Connected to 4 1/2" production casing - pumped 20 sxs cement.  
Connected to 8 5/8" surface casing - pumped 15 sxs cement.  
Max. P.S.I. 300#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3661	3663		LKC

Remarks: CONSOLIDATED OILWELL SERVICES, LLC -TICKET #28689.

Plugged through: TBG

District: 04

Signed

*Darrel Dipman*

(TECHNICIAN)

RECEIVED

DEC 27 2010 Form CP-2/3

KCC WICHITA

DEC 15 2010