

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-20817-00-013
Spot: NESESE Sec/Twnshp/Rge: 10-3S-27W
991 feet from S Section Line, 328 feet from E Section Line
Lease Name: GILLESPIE Well #: 5-10 INJ
County: DECATUR Total Vertical Depth: 3838 feet

Operator License No.: 3602
Op Name: PHILPOTT OIL & GAS CO INC
Address: 408 MAIN ST PO BOX 450
ATWOOD, KS 67730

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	260	0	160 SX
PROD	4.5	3836	0	600 SX

Well Type: EOR UIC Docket No: E25250.1 Date/Time to Plug: 12/16/2010 9:00 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: ROGER PHILPOTT Company: PHILPOTT OIL & GAS CO INC. Phone: (785) 626-3011

Proposed Plugging Method: Ordered 320 sxs 60/40 pozmix - 4% gel - 600# hulls.
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/16/2010 12:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 260' w/160 sxs cement.
4 1/2" production casing set at 3836' w/600 sxs cement.
TD 3838'. PBT 3675'.
Ran tubing to 2520' - pumped 160 sxs cement mixed with 300# hulls.
Pulled tubing to 1260' - pumped 115 sxs cement mixed with 100# hulls - cement to surface.
Pulled tubing to surface.
Connected to 4 1/2" production casing - pumped 20 sxs cement.
Connected to 8 5/8" surface casing - pumped 25 sxs cement.
Max. P.S.I. 300#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3648	3651		LKC

Remarks: CONSOLIDATED OILWELL SERVICES LLC-TICKET #28,691.

Plugged through: TBG

District: 04

Signed Darrel Dipman

(TECHNICIAN)

RECEIVED CM
DEC 27 2010 Form CP-2/3
KCC WICHITA ✓

DEC 17 2010