

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-039-20236-00-01  
Spot: SESE Sec/Twnshp/Rge: 10-3S-27W  
660 feet from S Section Line, 660 feet from E Section Line  
Lease Name: GILLESPIE WATER SUPPLY Well #: 1  
County: DECATUR Total Vertical Depth: 3840 feet

Operator License No.: 3602  
Op Name: PHILPOTT OIL & GAS CO INC  
Address: 408 MAIN ST PO BOX 450  
ATWOOD, KS 67730

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	270	0	200 SX
PROD	4.5	2299	0	600 SX

Well Type: WSW UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/16/2010 1:00 PM  
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC  
Proposal Rcvd. from: ROGER PHILPOTT Company: PHILPOTT OIL & GAS CO INC. Phone: (785) 626-3011

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 4% gel - 700# hulls.  
Plug through casing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/16/2010 2:15 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 270' w/200 sxs cement.  
4 1/2" production casing set at 2299' w/600 sxs cement.  
TD 3840'. PBTD 2299'.  
Well was reported to have been plugged on 02/28/1974.  
3115' of 5 1/2" casing pulled.  
Scout card indicated that well was washed down to 2299' with production casing already in the hole.  
12/16/2010 - 4 1/2" production casing observed in the well.  
Connected to 4 1/2" production casing - pumped 160 sxs cement mixed with 700# hulls.  
Max. P.S.I. 600#. S.I.P. 300#.  
Connected to 8 5/8" surface casing - pumped 20 sxs cement.  
Max P.S.I. 300#.

Perfs:

Top	Bot	Thru	Comments
1645	1675		
1428	1440		
1355	1390		
1205	1235		

Remarks: CONSOLIDATED OILWELL SERVICES LLC-TICKET #28,692.

Plugged through: CSG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

RECEIVED  
DEC 27 2010  
KCC WICHITA  
Form CP-2/3

DEC 17 2010