

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-21684-00-00
Spot: SESWSWSW Sec/Twnshp/Rge: 24-21S-24W
100 feet from S Section Line, 400 feet from W Section Line
Lease Name: GOEBEL UNIT Well #: #1-24
County: HODGEMAN Total Vertical Depth: 4583 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	206		WITH 150 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/08/2010 4:00 PM
Plug Co. License No.: 5123 Plug Co. Name: PICKRELL DRILLING COMPANY, INC.
Proposal Rcvd. from: MIKE KERNS Company: PICKRELL DRILLING COMPANY, I Phone: (316) 262-8427

Proposed Plugging Method: 1ST PLUG AT 1710' WITH 50 SX CMT. 2ND PLUG AT 810' WITH 80 SX CMT. 3RD PLUG AT 240' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: NONE
Date/Time Plugging Completed: 12/08/2010 4:30 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

Perfs:

1ST PLUG AT 1710' WITH 50 SX CMT. 2ND PLUG AT 810' WITH 80 SX CMT. 3RD PLUG AT 240' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

RECEIVED
DEC 17 2010
KCC WICHITA

Remarks: **8 5/8" SURFACE PIPE DID NOT CIRCULATE. RAN 1" TO 50' & PUMPED 140 SX CMT.** USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED
DEC 15 2010
KCC DODGE CITY

Signed _____

Jerry W Stapleton
(TECHNICIAN)