

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-21085-00-00
Spot: NWSESE Sec/Twnshp/Rge: 22-31S-13W
990 feet from S Section Line, 990 feet from E Section Line
Lease Name: PACKARD Well #: 3
County: BARBER Total Vertical Depth: 4225 feet

Operator License No.: 31406
Op Name: PRAIRIE RESOURCES, INC.
Address: 2530 NW WILLOW RD
MEDICINE LODGE, KS 67104

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3320		WITH 2 SX CMT
CIBP		3685		
SURF	8.625	322		WITH 250 SX CMT
PROD	4.5	4221	1356	WITH 275 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/06/2010 2:00 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: BOB PACKARD Company: PRAIRIE RESOURCES Phone: (620) 886-3431

Proposed Plugging Method: CIBP @ 3550' & 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 340' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE
Date/Time Plugging Completed: 12/06/2010 2:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 3320' WITH 2 SX CMT. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 340' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4218	4225		MISSISSIPPI OPEN
3596	3600		DOUGLAS
3363	3367		

RECEIVED
DEC 17 2010
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
DEC - 9 2010
KCC DODGE CITY

Signed Michael Maier
(TECHNICIAN)