

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-00373-00-01
Spot: NWNW Sec/Twnshp/Rge: 25-25S-16W
4651 feet from S Section Line, 4705 feet from E Section Line
Lease Name: JOHNSON Well #: 1
County: EDWARDS Total Vertical Depth: 4790 feet

Operator License No.: 5427
Op Name: D. R. LAUCK OIL CO., INC.
Address: 344 S LAURA
WICHITA, KS 67211

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10.75	338		WITH 225 SX CMT
PROD 7		4731	0	75 REG / 1000 LATEX

Well Type: SWD UIC Docket No: D07302.0 Date/Time to Plug: 12/20/2010 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MELVIN URBAN Company: D.R. LAUCK OIL CO. Phone: (620) 564-2013

Proposed Plugging Method: RUN TBG TO DEEPEST POINT & PUMP 50 SX CMT. RIP CASING @ 1060'. RUN TBG TO 1060' & ATTEMPT TO CIRCULATE CMT TO SURFACE 10 3/4" X 7" ANNULUS & UP 7".

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/20/2010 12:15 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

2 3/8" TBG & PACKER FISH @ 3484'. RAN TBG TO 3681'. PUMPED 50# HULLS, 10 SX GEL & 50 SX CMT. GOOD CIRCULATION. RIPPED 7" @ 1060' & COULDN'T MOVE CASING. RAN TBG TO 1054'. PUMPED 300 SX CMT DOWN TBG CIRCULATING CMT TO SURFACE UP 7". NO BLOW ON 10 3/4" X 7" ANNULUS. PULLED TBG & TOPPED OFF 7" WITH 60 SX CMT. PUMPED 150 SX CMT DOWN 10 3/4" X 7" ANNULUS. MAXIMUM PRESSURE 250#. SHUT IN PRESSURE 100 PSIG.

Perfs:

Top	Bot	Thru	Comments
4372	4382		
4333	4345		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: TBG

RECEIVED
DEC 29 2010

KCC WICHITA

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

RECEIVED
DEC 23 2010
KCC DODGE CITY

Form CP-213