

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-21012-00-00  
Spot: NWSESW Sec/Twnshp/Rge: 15-11S-20W  
990 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: ZACHMAN Well #: 6  
County: ELLIS Total Vertical Depth: 3625 feet

Operator License No.: 9067  
Op Name: DAMAR RESOURCES, INC.  
Address: 234 W 11TH STE A PO BOX 70  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1506	0	575 SX
PROD	5.5	3621	0	100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/10/2010 9:30 AM  
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE  
Proposal Rcvd. from: AVEN WEAVERLING Company: DAMAR RESOURCES, INC. Phone: (785) 623-3221

Proposed Plugging Method: Ordered 480 sxs 60/40 pozmix - 4% gel - 1/4# flocele - 500# hulls - 10 sxs gel.  
Removed CIBP at 1500'.  
Removed retrievable plug at 3400'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/10/2010 4:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

LK Wireline perfed two hole perforation at 1450'.  
Western Well Service RIH with tubing to 3460'.  
Quality Cementing rigged to tubing and mixed and pumped 10 sxs gel - followed with 50 sxs 60/40 pozmix with 150# hulls mixed in.  
Pulled tubing to 2060' - rigged to tubing and mixed and pumped 60 sxs 60/40 pozmix with 150# hulls.  
Pulled tubing to 1477'. Rigged to tubing and mixed and pumped 135 sxs cement with 100# hulls - circulated cement up 5 1/2" casing.  
Pulled tubing - rigged to 5 1/2" casing with a swedge and pumped 235 sxs cement down 5 1/2" casing - fluids circulated up 8 5/8".  
12/15/2010 - Topped off 5 1/2" and 8 5/8" casing with 5 1/2 yards cement slurry.  
Hole standing full.

Perfs:

Top	Bot	Thru	Comments
3572	3577		
3553	3558		
3376	3577		OA
3373	3380		

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4492.

Plugged through: TBG

District: 04

Signed *Pat Staab*  
(TECHNICIAN)

CM

RECEIVED  
DEC 21 2010

KCC WICHITA

Form CP-2/3

DEC 16 2010