

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-21593-00-00  
Spot: E2E2NWNW Sec/Twnshp/Rge: 8-31S-34W  
4619 feet from S Section Line, 4088 feet from E Section Line  
Lease Name: MLP YOUNG A Well #: 4  
County: SEWARD Total Vertical Depth: 5850 feet

Operator License No.: 5447  
Op Name: OXY USA INC.  
Address: 5 E GREENWAY PLZ PO BOX 27570  
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1716		WITH 500 SX CMT
DVT		2928		
PROD	5.5	5825	0	WITH 635 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/20/2010 2:00 PM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 300# HULLS & 25 SX CMT AT 5600'. PLUG AT 1740' WITH 50 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 60' WITH 10 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/20/2010 4:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

\*\*UNABLE TO GET ANY STRETCH ON CASING. WELL CEMENTED TO SURFACE.\*\* PUMP 300# HULLS & 25 SX CMT @ 5608'. 1ST PLUG AT 1800' WITH 25 SX CMT. 2ND PLUG AT 650' WITH 75 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5698	5704		CHESTER
5632	5650		CHESTER
5608	5614		CHESTER

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01

Signed Jack MacLaskey  
(TECHNICIAN)

RECEIVED  
DEC 22 2010  
KCC DODGE CITY

RECEIVED  
JAN 06 2011  
KCC WICHITA

Form CP-173