

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22152-00-00
Spot: SWSENE Sec/Twnshp/Rge: 18-7S-20W
2970 feet from S Section Line, 660 feet from E Section Line
Lease Name: LESAGE Well #: 4
County: ROOKS Total Vertical Depth: 3635 feet

Operator License No.: 33723
Op Name: PAUL BOWMAN OIL TRUST
Address: 801 CODELL RD
CODELL, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	246	0	170 SX
PROD	5.5	3634	0	200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/20/2010 10:30 AM
Plug Co. License No.: 33868 Plug Co. Name: RENEGADE WELL SERVICE LLC
Proposal Revd. from: DONALD A. BOWMAN Company: PAUL BOWMAN OIL TRUST Phone: (785) 434-2286

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 500# hulls.
Perfed at 1690' and 1020'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/20/2010 12:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2120' - pumped 270 sxs 60/40 pozmix - 4% gel with 300# hulls.
Pulled tubing to 1020' - pumped 95 sxs 60/40 pozmix - 4% gel with 200# hulls to circulate to surface.
Pulled all tubing. Topped off 5 1/2" casing with 10 sxs 60/40 pozmix - 4% gel.
Hooked to 8 5/8' x 5 1/2" annulus. Pumped 10 sxs 60/40 pozmix - 4% gel.
S.I.P. 250#.

Perfs:

Top	Bot	Thru	Comments
3520	3522		MARMINGTON / A
3418	3424		LANSING
3372	3374		LANSING
3334	3338		LANSING

RECEIVED
DEC 30 2010

Remarks: QUALITY OILWELL CEMENTING COMPANY-TICKET #4474.

KCC WICHITA

Plugged through: TBG

District: 04

Signed

Pat Bedore
(TECHNICIAN)

CM

Form CP-2/3

DEC 23 2010