

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-23688-00-00  
Spot: W2W2SW Sec/Twnshp/Rge: 11-9S-24W  
1320 feet from S Section Line, 330 feet from W Section Line  
Lease Name: RICE ESTATE Well #: 1-11  
County: GRAHAM Total Vertical Depth: 4110 feet

Operator License No.: 30717  
Op Name: DOWNING-NELSON OIL CO INC  
Address: PO BOX 372  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	305		180 SX

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/31/2010 8:00 PM  
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING  
Proposal Rcvd. from: TOM ALM Company: DOWNING-NELSON OIL CO INC Phone: (785) 621-2610

Proposed Plugging Method: Order 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER WitnessType: NONE  
Date/Time Plugging Completed: 10/31/2010 10:30 PM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

Perfs:

1st. Plug at 2170' w/25 sxs.  
2nd. Plug at 1300' w/100 sxs.  
3rd. Plug at 355' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.  
Mousehole with 15 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Ed Schumacher  
(TECHNICIAN)

CM

RECEIVED

DEC 23 2010

KCC WICHITA

Form CP-2/3

DEC 21 2010