

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-21051-00-01
Spot: SESENE Sec/Twnshp/Rge: 8-22S-4E
2984 feet from S Section Line, 411 feet from E Section Line
Lease Name: SPEIR OWWO Well #: 4
County: MARION Total Vertical Depth: 2414 feet

Operator License No.: 6131
Op Name: DRILLERS & PRODUCERS, INC.
Address: PO BOX 385
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	207		
PROD	4.5	2407	1009	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/30/2010 9:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: BILL ROGERS Company: _____ Phone: (620) 382-7212

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/03/2010 4:00 PM KCC Agent: SHANE JONES

Actual Plugging Report:

12/30/10 PHILLIPS RAN TUBING TO 2350', AND CONSOLIDATED PUMPED 50 SX OF CLASS A W/3% CACI. PHILLIPS PULLED TUBING. CONSOLIDATED RAN WIRELINE DOWN AND TAGGED CEMENT @ 2110'. DYNA-LOG RAN IN AND SHOT OFF CASING @ 1200'. CASING NOT FREE. DYNA-LOG RAN BACK DOWN AND SHOT OFF CASING @ 1009'. CASING IS FREE. PHILLIPS PULLED CASING. THEY THEN RAN TUBING BACK INTO 290'. CONSOLIDATED TIED ON AND BROKE CIRCULATION WITH WATER. THEY THEN SWITCHED TO CEMENT AND CIRCULATED 110 SXS OF CLASS A TO SURFACE. PHILLIPS PULLED TUBING, AND CONSOLIDATED TOPPED OFF THE WELL WITH 25 SXS CLASS A. FINISHED UP AT 4:00 PM TK #29840 185 SX CLASS A. 1/3/11 CHECKED TOP PLUG FINDING IT DOWN 12'. I TALKED TO BILL ROGERS. HE WILL DRY SACK TO SURFACE AND COVER UP.

Perfs:

Top	Bot	Thru	Comments
2367	2377	CSG	

RECEIVED
KANSAS CORPORATION COMMISSION
1-25-11
JAN 25 2011


Remarks: DENIED TA FOR HIGH FLUID LEVEL

CONSERVATION DIVISION
WICHITA, KS

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

1/3