

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22689-00-00
Spot: NWSENE SW Sec/Twnshp/Rge: 9-34S-38W
1970 feet from S Section Line, 2230 feet from W Section Line
Lease Name: EVELYN Well #: 9 #1
County: STEVENS Total Vertical Depth: 6800 feet

Operator License No.: 5278
Op Name: EOG RESOURCES, INC.
Address: 3817 NW EXPRESSWAY STE 500
OKLAHOMA CITY, OK 73112

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		6218		WITH 5 SX CMT
CIBP		6277		WITH 5 SX CMT
SURF	8.625	1621		WITH 500 SX CMT
PROD	4.5	6792	2962	WITH 230 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/17/2010 1:00 PM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUG PER KCC GUIDELINES AND REGULATIONS WHICH MAY INCLUDE: LOAD CSG W/ MUD, SET CIBP @ 6218' & CAP W/5 SX CMT, CUT & PULL FREEPIPE, MIX & SPOT 120 SKS CMT FROM 1674 - 1235', MIX & SPOT 50 SKS CMT FROM 730 - 570', TOP OUT W/15 SKS CMT FROM 64 - 4', DIGOUT/CUT OFF 4' BGL & WELD ON ID PLATE.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 12/17/2010 3:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 6218' WITH 5 SX CMT. 1ST PLUG AT 1670' WITH 120 SX CMT. 2ND PLUG AT 730' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6282	6301		
6268	6274		

Remarks: USED CLASS C CMT BY ORR ENTERPRISES.

Plugged through: TBG

RECEIVED
DEC 29 2010
KCC WICHITA

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
DEC 22 2010
KCC DODGE CITY

Form CP-1/3