

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-22652-00-00  
Spot: SWSESW Sec/Twnshp/Rge: 13-32S-37W  
319 feet from S Section Line, 3815 feet from E Section Line  
Lease Name: OLETA Well #: 13 #1  
County: STEVENS Total Vertical Depth: 7800 feet

Operator License No.: 5278  
Op Name: EOG RESOURCES, INC.  
Address: 3817 NW EXPRESSWAY STE 500  
OKLAHOMA CITY, OK 73112

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		6294		WITH 5 SX CMT
CIBP		6372		WITH 5 SX CMT
SURF	8.625	1613		WITH 480 SX CMT
PROD	4.5	6613	2769	WITH 194 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/15/2010 12:00 PM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 6290' WITH 5 SX CMT. PLUG AT 1640' WITH 15 SX GEL & 100 SX CMT. PLUG AT 610' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/15/2010 2:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

CIBP @ 6372' WITH 5 SX CMT. CIBP @ 6294' WITH 5 SX CMT. PLUG AT 1713' WITH 100 SX CMT. PLUG AT 610' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6380	6385		STLOUIS
6340	6346		ST LOUIS

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED  
DEC 17 2010  
KCC DODGE CITY

Signed Jack MacLaskey  
(TECHNICIAN)

RECEIVED  
DEC 27 2010  
KCC WICHITA  
Form CP-24