

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-23311-00-00  
Spot: SENWSESE Sec/Twnshp/Rge: 11-32S-10W  
918 feet from S Section Line, 770 feet from E Section Line  
Lease Name: SCHREINER FARMS "B" Well #: 1  
County: BARBER Total Vertical Depth: 4570 feet

Operator License No.: 31191  
Op Name: R & B OIL & GAS, INC.  
Address: 912 N LOGAN PO BOX 195  
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	252		WITH 190 SX CMT
PROD	5.5	4570	3420	WITH 125 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/28/2010 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 4350' & 5 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/28/2010 10:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4350' & PUT 5 SX CMT ON TOP OF SAND BRIDGE. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT W/100# HULLS. 2ND PLUG AT 280' WITH 50 SX CMT W/100# HULLS. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4400	4445		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed

Stephen J Pfeifer  
(TECHNICIAN)

RECEIVED  
JAN - 6 2011  
KCC DODGE CITY

RECEIVED  
KANSAS CORPORATION COMMISSION  
JAN 21 2011  
Form CP-2/3

CONSERVATION DIVISION  
WICHITA, KS