

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-019-19264-00-01
Spot: SWNENWSE Sec/Twnshp/Rge: 27-33S-11E
2140 feet from S Section Line, 1980 feet from E Section Line
Lease Name: WADSWORTH Well #: 3
County: CHAUTAUQUA Total Vertical Depth: 1248 feet

Operator License No.: 33157
Op Name: R. D. ENERGY, INC.
Address: 905 N MONTGOMERY
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10	443		30 sx to surface
PROD	7	1226		

Well Type: EOR UIC Docket No: E21797.1 Date/Time to Plug:
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: ROD DICKENS Company: Phone: (620) 725-3065

Proposed Plugging Method: Pull tbg & pkr. TIH w/1" to TD, gell hole, spot 100' cement plug on bottom. Set 50' middle plug @ 700', set 350' cement plug to surface. Cut off and clean location.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed 09/16/2010 8:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report: Perfs:

Pulled tubing and packer out of well. Perforated casing at 700' and 350'. Ran 1" to 1230' gelled hole and spotted 20 sack plug. Pulled 1" up to 700' and spotted 10 sack plug. Pulled 1" up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 192 sacks of cement were used to plug this well.

RECEIVED
NOV 30 2010 DAS
KCC Chanute Dist. #3

RECEIVED
DEC 17 2010
KCC WICHITA

Remarks:
Plugged through: TBG

District: 03 Signed [Signature] (TECHNICIAN)