

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-003-22032-00-00

Spot: NWNWSESW

Sec/Twnshp/Rge: 16-22S-19E

1101 feet from S Section Line,

3777 feet from E Section Line

Lease Name: BOOTS

Well #: 7

County: ANDERSON

Total Vertical Depth: 849 feet

Operator License No.: 33097

Op Name: SOUTHERN STAR CENTRAL GAS PIPE

Address: 4700 HWY 56

OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
--------	------	------------	-------------	---------

SURF	6.25	49		NO SXS LISTED
------	------	----	--	---------------

PROD	2.5	849		NO SXS LISTED
------	-----	-----	--	---------------

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 10/06/2010 1:00 PM

Plug Co. License No.: 34059

Plug Co. Name: HURRICANE SERVICES, INC.

Proposal Rcvd. from: STEVE BENJAMIN

Company:

Phone: (785) 448-4804

Proposed Plugging Method: TIE TO 2/12"- ESTABLISH FLOW RATE & SQUEEZE CEMENT INTO FORMATION UNTIL DESIRED AMOUNT OF CEMENT AND PRESSURE IS ACHIEVED, FILLING WELL TO SURFACE. CUT OFF PIPE 3 FT. BELOW SURFACE, CUT, CAP AND BACKFILL.

Plugging Proposal Received By:

Witness Type: NONE

Date/Time Plugging Completed 10/06/2010 3:00 PM

KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 1-INCH PIPE IN 2-INCH PIPE AND PUMP CEMENT FROM TD (849 FEET) TO SURFACE. PULL PIPE THEN HOOK ON TO 2-INCH AND SQUEEZE CEMENT AT 900 PSI. A TOTAL OF 63 SACKS OF CEMENT WERE USED TO PLUG THE WELL.

Perfs:

Top	Bot	Thru	Comments
823	827		

RECEIVED

JAN 12 2011

KCC Chanute Dist #3

Remarks:

Plugged through: TBG

District: 03

Signed L. Short

(TECHNICIAN)

KANSAS CORPORATION COMMISSION

1-18-11
JAN 18 2011

Form CP-2/3

RECEIVED